

INVITATION FOR BIDS

JULY 16, 2026, 11:00 A.M. CENTRAL LOCAL TIME, BELCOURT, ND:

CONSTRUCTION OF THE GREEN ACRES LAGOON RENOVATION ON THE TURTLE MOUNTAIN RESERVATION, ROLETTE COUNTY, NORTH DAKOTA

The Turtle Mountain Band of Chippewa will accept bids from qualified contractors for the construction of the Green Acres Lagoon Renovation project on the Turtle Mountain Reservation, Rolette County, North Dakota

Sealed bids will be accepted until 11:00 A.M. Central Local Time, July 16, 2026, at which time a public bid opening will be held at the conference room of the Turtle Mountain Public Utilities Commission, 1001 Chief Little Shell st. Belcourt, ND 58316.

PLANS AVAILABLE FROM TRIBE: A bid package may be obtained from the Turtle Mountain Public Utilities Commission, PO Box 490, Belcourt, North Dakota, 701-477-6159, ATTN: Kenneth J. Azure. A nonrefundable fee of \$125 will be charged for each bid package or an emailed pdf will be made available upon request at no charge by contacting Kenneth J. Azure, puckenny@utma.com. Additionally, a bid package may be obtained from the Quest Construction Data Network (www.questcdn.com), Project Number TM2026-CSL-1. Delivered bids will be read during the bid opening.

A copy of a valid Contractor's license for the state in which the work resides or Certification of Renewal thereof issued and registration of Indian owned firm from TERO shall be supplied at the time of bidding and enclosed in the required Bidder's Bond envelope.

ENGINEER: Indian Health Service, DSFC, Minot, ND.

INDIAN PREFERENCE: In the evaluation of the bids, the Owner may, within funding limitations, give preference up to the amount of 10% above the lowest total bid, to qualified Indian owned firms. The qualified Indian owned firms must register with the local TERO Office prior to the bid opening.

PROJECT DESCRIPTION: The scope of work includes furnishing all labor, equipment and materials for the construction of the following:

- Rehabilitation of an existing waste water treatment system consisting of a 9.1 acre primary cell and 8.1 acre secondary cell, a new 3.43 acre constructed wetland, new wetland access road, cut volume for constructed wetland site work is 21,250 cubic yards, wetland inlet and outlet flow control structures, 1,823 feet of 8-inch PVC SDR 21 gravity sewer main, new inlet manhole and connection to existing sewer force main, new lagoon structures, removal and abandonment of existing lagoon structures, 4,000 cubic yards of rip-rap, removal of existing fence, 4,580 linear feet of new chain link fence, and other related items to complete the project as shown on the plan drawings and stated in the specifications

CONTRACT DURATION: Contract will proceed with available funding from the date of the Notice to Proceed and shall be complete with the entire work ready for use no later than Two Hundred Fifty (250) calendar days after the Notice to Proceed.